

1 060635

API NUMBER 15- 185-22,263-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE NW, SEC. 29, T 23 S, R 13 W
2970 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7916

Lease Name Cornwell Well # 1

Operator: Eldon J. Schierling-Dynoil, Inc.
Name & Address: 850 Sutton Place
Wichita, KS 67202

County Stafford (Arbuckle) 130.49
Well Total Depth 4015 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 333

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Co. License Number 5418

Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 10:00 am Day: 4 Month: August Year: 19 85

Plugging proposal received from Don Kern

(company name) Allen (phone) 316-793-5681

Elevation N/A

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 776'

- 1st plug at 4010' with 40 sx cement
- 2nd plug at 780' with 40 sx cement
- 3rd plug at 290' with 50 sx cement
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:15 pm Day: 4 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 4010' with 40 sx cement, 2nd plug at 780' with 40 sx cement, 3rd plug at 290' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

8-13-85 AUG 13 1985

Remarks: Used 60/40 pozmix 6% gel by BJ-Titan

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(check) do not observe this plugging.

DATE 8-14-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 9594

8-SEP 11 1985