

To: 1 040799 11-4
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,433-00-01
C NE SW , SEC. 28 , T 23 S, R 13 W/E
1980 feet from S section line
1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # - 6141
Operator: Coronado Oil & Gas, Inc.
Name:
Address P.O. Box 1285
Great Bend, KS 67530

Lease Name O'Conner OWWO Well # 1-28
County Stafford
Well Total Depth 4005 130.16 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 402

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 4 Month: 11 Year: 19 93

Plugging proposal received from Joe Maes
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4000' w/185 sx cement, PBTD 3954', Perfs at 3575-78, 3681-85, 3704-08'
1st plug sand back to 3525' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2:15 p.m. Day: 4 Month: 11 Year: 19 93.

ACTUAL PLUGGING REPORT 1st plug sanded back to 3525' and dumped 4 sx cement on top of sand
bridge through bailer.
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement. 11-12-93
Maximum pressure 750 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1902' of 4 1/2" casing.
Additional description is necessary, use BACK of this form.)
observe this plugging.

INVOICED
NOV 16 1993
DATE
INV. NO. 39191

RECEIVED
STATE CORPORATION COMMISSION
NOV 12 1993
CONSERVATION DIVISION
Wichita, Kansas
Signed Stephen J. [Signature]
(TECHNICIAN)
FORM CP-2/