

1 040220
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-20
API NUMBER 15-185-22.445-6000

TECHNICIAN'S PLUGGING REPORT

Operator License # 9324

Operator: JFW, Inc.

Name &

Address RR 1, Box 26

Plevna, KS 67568

1-24-89 App. 4950 feet from S section line

App: 3630 feet from E section line

Lease Name Smith Well # 1-30

County Stafford

Well Total Depth 4075 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 20 Month: 1 Year: 1989

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4049' PBSD 3993' Perfs at 3554-56, 3568-60, 3688-92, 3696-98'

1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:30 a.m. Day: 20 Month: 1 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 120 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2300' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 1-25-89

INV. NO. 23781

Signed

Stephen J. Pfeifer
(TECHNICIAN)