

8-5 15-185-22-472-0000 54
API NUMBER 15- Docket #D-25,327

To: 1 120606
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW NE, SEC. 11, T 23 S, R 13 W/E
4290 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9247

Lease Name Postlethwaite Well # 1
County Stafford 130.81
Well Total Depth 4025 feet

Operator: Cincris Energy Company Inc.
Name & Address 22026 Tanbark Lane
El Toro, CA 92630

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ X D&A
Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 8 a.m. Day: 5 Month: 8 Year: 19 91

Plugging proposal received from Bill Riley
(company name) Cincris Energy Company Inc. (phone) 316-792-6228

were: 4 1/2" at 3927', TOC @ 3520', Open hole
1st plug circulate cement from below anhydrite to bottom of cellar through tubing.

Unable to get tubing inside of 4 1/2" casing at 309', washed down with tubing in annulus to 823'.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5:30 p.m. Day: 5 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 2 3/8" tubing washed down to 823' and perforated 4 directions and
circulated cement with 490 sx. Circulated hole with 240 bbl. drilling mud prior to cementing.
Tagged plug on 8/6/91-TOC 25' from surface.

8-13-91

Remarks: Used 60/40 Pozmix 6% and 4% gel by HOWCO. Recovered 309' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE SEP 06 1991

RECEIVED STATE CORPORATION COMMISSION
AUG 13 1991 Signed Duane Rankin (TECHNICIAN)

INV. NO. 32963 NOV 20 1991
8-5

CONSERVATION DIV. Wichita, Kansas