

To: 1 060643  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,261-0000  
NW SW NE , SEC. 11, T 23 S, R 13 WXX  
3630 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131  
Operator: Thunderbird Drilling, Inc.  
Name & Address: P. O. Box 18407  
Wichita, KS 67218

Lease Name Wesley "A" Well # 1  
County Stafford 125.48  
Well Total Depth 3861 (Arubckle) feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Thunderbird Drilling, Inc. License Number 5131  
Address P. O. Box 18407, Wichita, KS 67218

Company to plug at: Hour: 11:00 pm Day: 17 Month: August Year: 19 85

Plugging proposal received from Ed Cook

(company name) Thunderbird (phone) 316-685-1441

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1900'  
Anhydrite 750'

- 1st plug into the arbuckle with 40. sx cement
- 2nd plug in the base of the anhydrite with 50 sx cement
- 3rd plug 30' out of the surface pipe with 50 sx cement
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:30 am Day: 17 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 3850' with 40 sx cement, 2nd plug at 750' with 50 sx  
cement, 3rd plug at 375' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with  
15 sx cement.

8-20-85

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

INVOICED  
DATE 8-20-85  
INV. NO. 9695-8-17

AUG 20 1985