

To: 1 052061  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 185-22,189 - 0000  
100' S of  
NE SE NW, SEC. 11, T 23 S, R 13 W/X  
3530 feet from S section line  
2970 feet from E section line

8-9

TECHNICIAN'S PLUGGING REPORT

Operator License / 5893  
Operator: Pratt Well Service  
Name: P.O. Box 847  
Address: Pratt, KS 67124

Lease Name Firebaugh Well # 1  
County Stafford 127.40  
Well Total Depth 3920 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893  
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 11 a.m. Day: 9 Month: 8 Year: 19 96

Plugging proposal received from Kenneth Gates  
(company name) Pratt Well Service (phone) 316-672-2531

Work: 5 1/2" at 3919' w/100 sx cement, PBSD 3832', Perfs at 3860-62, 3496-99, 3618-22  
1st plug sand back to 3565' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 9 Month: 8 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 3565' and dumped 5 sx cement on top of sand through bailer,  
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 12 sx gel, 50 sx cement 8 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 100 psi;

RECEIVED  
STATE CORPORATION COMMISSION  
8-14-96  
AUG 14 1996

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1894' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

I (and/or representative) observe this plugging.

DATE 8-16-96

Signed Richard W. Lacy  
(TECHNICIAN)

INV. NO. 46275  
8-9