

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-27397-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 9-29S-14E
330 feet from S Section Line, 1980 feet from E Section Line
Lease Name: C. MAYESKE Well #: A-4
County: WILSON Total Vertical Depth: 1280 feet

Operator License No.: 33539
Op Name: CHEROKEE WELLS LLC
Address: 5201 CAMP BOWIE BLVD STE 200
FT WORTH, TX 76107

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1269		135 SX
SURF	8.625	41		10 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 01/31/2017 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JEFF MORRIS Company: CHEROKEE WELLS LLC Phone: (620) 378-3650

Proposed Plugging Method: Set 10 sack cement plug on TD to approx. 1125'. Fill to 600' with gel, then set 10 sack cement plug to approx. 455'. Fill with gel to approx. 350', then cement to surface.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 01/31/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:
A 2.375" cement string was lowered to 1269 ft. 10 sacks of cement were then spotted. The cement string was pulled to 600 ft and 10 sacks of cement were spotted. The cement string was pulled to 350 ft and the well filled to surface with cement; gel spacers between. A total of 50 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DIST # 3
APR 19 2017
CHANUTE, KS

AD

KCC WICHITA
APR 24 2017
RECEIVED

Remarks:

Plugged through: CSG

4-24-17

District: 03

Signed Alan Dunning
(TECHNICIAN)
INVOICED
MAY - 3 2017