

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-27836-00-00
Spot: SESWSWNE Sec/Twnshp/Rge: 36-30S-14E
2455 feet from N Section Line, 2145 feet from E Section Line
Lease Name: GORTON Well #: 7P-36
County: WILSON Total Vertical Depth: 1267 feet

Operator License No.: 33365
Op Name: LAYNE ENERGY OPERATING, LLC
Address: 610 S. 38TH STREET
KANSAS CITY, KS 66106

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1243		135 SX
SURF	8.625	42		16 SX
T1	2.375	1185		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2017 12:00 PM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: PATRICK LOVE Company: LAYNE ENERGY OPERATING Phone: (281) 475-2579

Proposed Plugging Method: Per KCC Rules and Regulations: Spot cement plugs at TD, Middle, and 200 ft to surface, gel spacers between.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 01/31/2016 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered into hole to 1130 ft and a 50 ft cement plug spotted. The cement string was pulled to 700 ft and a 50 ft cement plug spotted. The cement string was pulled to 225 ft and the well filled to surface with cement; gel spacers between cement plugs. A total of 34 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
1147	1158		
RECEIVED KCC DIST #3 APR 19 2017 CHANUTE, KS AD 4-24-17 KCC WICHITA			

Remarks:

Plugged through: CSG

APR 24 2017
RECEIVED

District: 03

Signed Alan Dunning

(TECHNICIAN)
INVOICED
MAY - 3 2017