

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-27835-00-00
Spot: SENESENE Sec/Twnshp/Rge: 26-30S-14E
495 feet from N Section Line, 185 feet from E Section Line
Lease Name: BAKER Well #: 1A-26
County: WILSON Total Vertical Depth: 1287 feet

Operator License No.: 33365
Op Name: LAYNE ENERGY OPERATING, LLC
Address: 610 S. 38TH STREET
KANSAS CITY, KS 66106

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 4.5 | 1274 | | 135 SX |
| SURF | 8.625 | 42 | | 16 SX |
| T1 | 2.375 | 1214 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/01/2017 12:00 PM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: PATRICK LOVE Company: LAYNE ENERGY OPERATING Phone: (281) 475-2579

Proposed
Plugging
Method:

Per KCC rules and regulations: Spot cement plugs at TD, middle, and 200 ft to surface, gel spacers between

Plugging Proposal Received By: ALAN DUNNING WitnessType: PARTIAL
Date/Time Plugging Completed: 02/01/2017 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was lowered into well to 1140 ft. A 50 ft cement plug was spotted. The cement string was pulled to 700 ft and a 50 ft cement plug spotted. The cement string was pulled to 225 ft and the well was filled to surface with cement; gel spacers between cement plugs. A total of 35 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1173 | 1175 | | |
| 1160 | 1169 | | |

RECEIVED
KCC DIST # 3
APR 19 2017
CHANUTE, KS

AD
KCC WICHITA
APR 24 2017

RECEIVED

4-24-17

Remarks:

Plugged through: CSG

District: 03

Signed Alan by. Dunning
(TECHNICIAN)

INVOICED
MAY - 3 2017