

1 030692

API NUMBER 15- 185-21,180-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE SE, SEC. 3, T 22 S, R 13 (W) W  
2310 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7617

Lease Name Fischer Well # 1

Operator: Lytton Oil Production  
Name & Address 281 S. Highway, Box 262  
Great Bend, KS 67530

County Stafford 123.83  
Well Total Depth 3810 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 17 Month: April Year: 19 86

Plugging proposal received from Ronny Hoover

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3809' Perfs at 3346-48'; 3362-64'; 3491-94'; 3532-35'; 3619-22'; 3731-36'  
1st plug sand back to 3295' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 5 sx hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 11:30 am Day: 17 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3295' and dumped 5 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 5 sx hulls, released 8 5/8" rubber  
plug and pumped 100 sx cement.

4-28-86  
RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1986  
CONSERVATION DIVISION  
Wichita, Kansas

Shut in pressure 250 psi

Remarks: Used Econolite cement by Halliburton, Recovered 2833' 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED (copy of invoice) observe this plugging.

Signed Steve Durrant  
(TECHNICIAN)

DATE APR 29 1986

INV. NO. 13589 4-17