

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-10895-00-01
Spot: NWSEW Sec/Twnshp/Rge: 3-22S-13W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: GATES B Well Number: 2
County: STAFFORD Total Vertical Depth: 3792 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

Production Casing Size: 4.5 feet: 3791
Surface Casing Size: 8.625 feet: 250

8/23.24

Well Type: EOR UIC Docket No: E23105.1 Date/Time to Plug: 05/01/2003 8:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: KEN GATES Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: CIBP @ 3450'. RUN TUBING TO 3446. PUMP 10 SX CMT. PULL TUBING. CIRCULATE CMT TO SURFACE. TOP OFF.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/01/2003 3:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 3590'. PERFS AT 3501-3554'. 4 1/2" SQUEEZED AT 722' WITH 150 SX CMT. SQUEEZED AT 440' WITH 200 SX CMT. SET CIBP @ 3450'. RAN TUBING TO 3446'. PUMP 10 SX CMT & DISPLACE WITH 10 BBL. PULED TUBING TO 750'. CIRCULATED CMT TO SURFACE UP 4 1/2" WITH 60 SX CMT. PULLED TUBING OUT OF HOLE. TOPPED OFF 4 1/2" WITH 5 SX CMT.

RECEIVED
MAY 13 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED CEMENTED TO SURFACE 722-0'.

Plugged through: TBG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 5-14-03
INV. NO. 2003061522