

15.185.10893.0000

4-2

1052237
TO: STATE CORPORATION COMMISSION

API NUMBER 15- Drilled 1953
NE NE NW, SEC. 3, T 22 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 4950 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GATES WELL # A-6

TECHNICIAN'S PLUGGING REPORT

COUNTY Stafford 122.36

OPERATOR LICENSE # 5893

WELL TOTAL DEPTH 3765 FEET

OPERATOR: PRATT WELL SERVICE, INC PRODUCTION CSG: SIZE 5 1/2" FEET 3650'

NAME AND P.O. BOX 847 SURFACE CASING: SIZE 8 5/8" FEET 250'

ADDRESS PRATT, KS 67124-0847

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR PRATT WELL SERVICE, INC LICENSE NUMBER 5893

ADDRESS P. O. BOX 847, PRATT, KS 67124-0847

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 2 MONTH: APRIL YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KENNETH GATES

(COMPANY NAME) PRATT WELL SERVICE INC. (PHONE) 316-672-2531

WERE: PERFORATIONS 3506'-10' CASING LEAK @ 3119' PBT 3521' WITH A CIBP

RUN TUBING TO PERFORATIONS AND PUMP DOWN TUBING WITH 25 SX OF GEL FOLLOWED BY 20 SX OF CEMENT

DISPLACE CEMENT TO BOTTOM. PULL TUBING TO 700' AND CIRCULATE CASING FULL OF CEMENT TO

TO SURFACE. PUMP 8 5/8" X 5 1/2" ANNULAS FULL OF CEMENT UNTIL IT PRESSURES UP

5 1/2" CASING HAD BEEN SQUEEZED AT 304' TO 310' WITH 300 SX OF CEMENT.

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 3:45 PM DAY: 2 MONTH: APRIL YEAR: 1998

ACTUAL PLUGGING REPORT RAN TUBING TO TO 3510'. PUMPED 25 SX OF GEL WITH 250# OF

COTTENSEED HULLS MIXED IN FOLLOWED BY 20 SX OF CEMENT WITH 50# OF COTTENSEED

HULLS MIXED IN. THIS WAS DISPLACED WITH 5 SX OF GEL. PULLED TUBING TO 700'

CIRCULATED CEMENT TO SURFACE USING 90 SX OF CEMENT

PRESSURED ANNULAS TO 2000 PSI DID NOT GET ANY CEMENT IN.

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1998
APR 4-8-98

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lucey
(TECHNICIAN)

FORM CP-2/3

INVOICED

DATE 4-15-98

WEL. NO. 50357