

To: 1041301 3-27  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-185-20890-0000  
NWSENE SEC. 3, T 22 S, R 13 W/4

TECHNICIAN'S PLUGGING REPORT

RECEIVED  
KANSAS CORP COM.

feet from S section line  
feet from E section line

Operator License 16357

1998 APR -9 12:26

Lease Name Kisner "B" Well 1 2

Operator: Webco Oil Company 4-9-98  
Name:  
Address: 1303 Baker Ave.  
Great Bend, Ks. 67530

County Stafford 120.97  
Well Total Depth 3722 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 291'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 467 Chase, Kansas

Company to plug at: Hour: 8:45am Day: 27 Month: 3 Year: 19 98

Plugging proposal received from Monti Andrews

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

work: 5 1/2" @ 3715' w/ NA 5x of cement, PBTDC N.A., Top Perfs @ 3370-74, Bottom Perfs @ 3650-60

1<sup>st</sup> plug sand back to 3320' & put 5sx. cement on top of sand through bailer.

2<sup>nd</sup> plug lay down 5 1/2" casing + trip tbg. in hole to 500'. Circulate hole from 500' to surface w/ cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:30am Day: 27 Month: 3 Year: 19 98

ACTUAL PLUGGING REPORT 1<sup>st</sup> plug sanded back to 3320' & dumped 5sx. cement on top of sand bridge through bailer,

2<sup>nd</sup> plug circulated hole through tubing from 500' to surface w/ 185sx. cmt. Pulled tubing out of hole + topped well out w/ 65sx. cmt. [staged cmt. in]

Remarks: used 60/40 poz mix by Allied. Recovered 320' of 5 1/2" casing. Casing had parted @ 320' (if additional description is necessary, use BACK of this form.)

INVOICED

1 (did not) observe this plugging.  
DATE APR 15 1998

INV. NO. 50348

Signed Stephen J. Pfeiffer (TECHNICIAN)