

1070078

TO: STATE CORPORATION COMMISSION

8-6

API NUMBER N/A 15-185-11198-0000
SE SW NW SEC. 2, T 22 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 2970 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4290 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BATMAN WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD

OPERATOR LICENSE # 6458

WELL TOTAL DEPTH 3695 120.09 FEET

OPERATOR: POORBOY CORPORATION

PRODUCTION CSG: SIZE 7 " FEET 3695'

NAME AND RT 2- BOX 109 A

SURFACE CASING: SIZE 10 3/4" FEET 419'

ADDRESS ELLINWOOD, KS 67526

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE, INC

LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 05 MONTH: 8 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE, INC (PHONE) 316-727-3410

WERE: PERFS AT 3388 TO 3392 PBTD AT 3695

1ST PLUG SAND BACK TO 3297' WITH 7 SX PORTLAND

2ND PLUG WITH 15 SX GEL & 50 SX CEMENT AT 700'

3RD PLUG WITH 70 SX CEMENT AT 430'

4TH PLUG WITH 15 SX CEMENT AT 40'

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 06 MONTH: 8 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SAND BACK TO 3297' WITH 7 SX PORTLAND, 2ND PLUG WITH 15 SX GEL & 50 SX CEMENT

AT 700', 3RD PLUG WITH 70 SX CEMENT AT 430', 4TH PLUG WITH 15 SX CEMENT AT 40'

GOOD CIRCULATION. *PLUG FELL TO 412'. 5TH PLUG AT 370' SPOTTED 50 SX CEMENT THROUGH

TUBING, 6TH PLUG AT 270' SPOTTED 10 SX GEL THROUGH TUBING, 7TH PLUG AT 150' CIRCULATED

APPROXIMATELY 90 SX CEMENT THROUGH TUBING.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2418' OF 7" CASING

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID NOT OBSERVE THIS PLUGGING.

SIGNED

(TECHNICIAN)

FORM CP-2/3

INVOICED

DATE

AUG 14 1998

INV. NO.

57121

RECEIVED
KANSAS SDRP COM
1998 AUG 10 12:15

8-10-98