

1 120784

4-21

15-185-00039-0000

38R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 1/22/57

NE NE NE, SEC. 2, T 22 S, R 13 W XX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Bunselmeyer Well # 1

Operator: BEREXCO, INC.

County Stafford 121.87

Name & Address P.O. Box 723

Well Total Depth 3750 feet

Hays, KS 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 283

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor BEREXCO, INC. License Number 5363

Address P.O. Box 723, Hays, KS 67601

Company to plug at: Hour: 5 p.m. Day: 21 Month: 4 Year: 19 93

Plugging proposal received from Dennis Kirmer

(company name) BEREXCO, INC. (phone) 913-628-6101

were: 5 1/2" at 3750' w/150 sx cement, PBD 3712', Perfs at 3449-3515'-KC & 3655-93'-Arbuckle
1st plug set CIBP at 3600',

2nd plug fill 5 1/2" with cement,

3rd plug pump 150 sx cement between 8 5/8" X 5 1/2" annulus.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:15 p.m. Day: 21 Month: 4 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3600',

2nd plug pumped into 5 1/2" casing with 325 sx cement. Pumping pressure 0-200 psi and shut in 50 psi.

3rd plug pumped into 8 5/8" X 5 1/2" annulus with 150 sx cement. Pumping pressure 0-200 psi and shut in 50 psi.

4-26-93

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 65/35 Pozmix 6% gel by Allied. No casing recovery.

APR 26 1993

INVOICED

(Additional description is necessary, use BACK of this form.)

DATE 4-27-93 (old / observe this plugging.)

CONSERVATION DIVISION

INV. NO. 37618

Signed [Signature] (TECHNICIAN)