

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21460-00-00
Spot: CNWNWNE Sec/Twnshp/Rge: 2-22S-13W
4950 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: FISCHER - A Well Number: 1
County: STAFFORD Total Vertical Depth: 3800 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 270
Production: Size 5.5 feet: 3798 WITH 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/13/2001 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND BACK TO 3750' & 5 SX CMT. 1ST PLUG AT 730' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 10 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 03/13/2001 5:40 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE AT 3798-3800'. SANDED TO 3745' & 5 SX CMT WITH BAILER. PUMPED PLUGS THROUGH CASING. 1ST PLUG AT 730' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED
DATE 3-20-2001
WVZ NO. 200.1061517

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2400' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Steve A. Kurovich for RWC
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION **MAR 15 2001**

Form CP-2/3

3-19-01

MAR 19 2001

CONSERVATION DIVISION
WICHITA, Kansas

MP

W