

To: 1 121089
STATE CORPORATION COMMISSION
Wichita State Office Bldg. **PLUGGING SECTION**
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-11192-0000

8/2 NW SW, SEC. 2, T 22 S, R 13 W/E
1650- feet from S section line
4620- feet from E section line

12-6

TECHNICIAN'S PLUGGING REPORT

Operator License # 6357

Lease Name Batman Well # 1

Operator: WEBCO Oil Company

County Stafford

Name & Address 1303 Baker Ave.

Well Total Depth 3696 120.12 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 12 Year: 19 95

Plugging proposal received from Nick M. Weber

(company name) WEBCO Oil Company (phone) 316-793-8756

work: 5 1/2" at 3686' w/100 sx cement, Perf at 3355', 4 1/2" liner top to bottom

1st plug pump in 4 1/2" liner with 200 lbs. hulls and 25 sx cement, displace to 3000'

2nd plug perforate 4 1/2" liner and 5 1/2" casing at 700' and circulate with 280 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 6 Month: 12 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" liner with 200 lbs. hulls and 25 sx cement, displaced to 3000',

2nd plug perforated 4 1/2" liner and 5 1/2" casing at 700' and circulated with 280 sx cement.

DEC 20 1995
12-20-95

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 09 1996

INV. NO. 44479

Signed Duane Rankin
(TECHNICIAN)