

To: 1 120759 12-10
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 5/53 15-185-00229-0001

NW SW NE, SEC. 2, T 22 S, R 13 W/R

3630 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Brunselmeyer Well # 3

Operator: BEREXCO INC.

County Stafford 119.15

Name & Address 970 Fourth Financial Ctr.

Well Total Depth 3666 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor BEREXCO INC. License Number 5363

Address 970 Fourth Financial Ctr., Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 10 Month: 12 Year: 19 92

Plugging proposal received from Bob Grant

(company name) BEREXCO INC. (phone) 316-265-3311

were: 5 1/2" at 3656', Open hole 3656-66', Perfs at 3336-48', Holes in casing at 261-291', 2030', 4 1/2" liner from 0-382' & 2542'

1st plug pump 20 sx cement at 3656' through tubing,

2nd plug pump 20 sx cement at 3300', circulate mud,

3rd plug pump cement at 650-0'.to fill.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 10 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT Bottom of hole filled with sand to 3000'.

Ran tubing to 3000' and pumped 80 bbl. drilling mud. Pumped 40 sx cement at 3000'.

Pulled tubing to 650' and circulate cement with 200 sx cement.

Laid down all tubing and squeezed 5 1/2" and 5 1/2" X 8 5/8" annulus with 60 sx cement.

No pressures.

12-13-92

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 382' of 4 1/2" liner, no 5 1/2" casing recovered. (If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION

DEC 7 5 1992

I did observe this plugging.

DATE 1-6-93

Signed [Signature] (TECHNICIAN) Wichita, Kansas

INV. NO. 37112