

1 120074

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3243

Operator: Commonwealth Petroleum Corporation
Name & Address: 2704B Nottingham
Hutchinson, KS 67502

2-27-88 15-185-21833-0000
API NUMBER 15- Drill Completion Date 8/29/83

SE NW SW, SEC. 34, T 23 S, R 13 W/E
1650 feet from S section line
4290 feet from E section line

Lease Name Delp Well # 1
County Stafford 128.54

Well Total Depth 3955 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 403

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Box 108, Geneseo, KS

Company to plug at: Hour: 10 a.m. Day: 27 Month: 2 Year: 19 88

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6467

were: 5 1/2" at 3935' PBDT 3530' Perfs at 3480-85'

1st plug sand back to 3430' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 27 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3430' with 5 sx cement on top through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls,

10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped

100 sx cement. 3-4-88

Pumping pressure 0-600 psi and shut in 200 psi.

Checked top of plug on 2/29/88. It was at 13'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE 3-4-88

INV. NO. 20012

Signed Duane Rankin (TECHNICIAN)