

2-27-88 15-185-22165-0000

To: 1 120075
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 11/23/85

NE NE SE, SEC. 33, T 23 S, R 13 W/E
2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3243

Lease Name City St. John Well # 1

Operator: Commonwealth Petroleum Corporation
Name & Address: 2704B Nottingham
Hutchinson, KS 67502

County Stafford 129.68

Well Total Depth 3990 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 341

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Box 108, Geneseo, KS

Company to plug at: Hour: 12 p.m. Day: 27 Month: 2 Year: 19 88

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6467

were: 5 1/2" at 3970' PBT'D 3588' Perfs at 3536-44'

1st plug sand back to 3480' and dump 5' sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 27 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3480' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 150 lbs. hulls, and 100 sx cement.

Pumping pressure 0-600 psi and shut in 200 psi.

Checked top of plug on 2/29/88. It was at 11'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Threads were bad in 8 5/8" collar-had plate welded on.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 3-4-88

INV. NO. 20013