

1 070408

SEP 8 1987

15-185-21429-0500

API NUMBER 15- Docket #D-20,437

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

Q N/2 NE, SEC. 33, T 23 S, R 13 (W/2)

4620 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name Hager Well # 3

Operator: Davis Petroleum, Inc.

County Stafford 134.88

Name & Address Rt. 1, Box 183B

Well Total Depth 4150 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:24 p.m. Day: 8 Month: 9 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3997' Open hole Elevation 1904' KB

1st plug sand back to 2945' and dump 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:45 p.m. Day: 8 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3947' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

STATE CORPORATION COMMISSION

SEP 10 1987 9-10-87

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2720' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Dan Goodson (TECHNICIAN)

DATE SEP 11 1987

INV. NO. 18076