

1 070407

SEP 8 1987

15-185-21391-0000

API NUMBER 15- Completion date 8/21/81

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C S/2 NE, SEC. 33, T 23 S, R 13 W/EX

3300 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name Hager Well # 2

Operator: Davis Petroleum, Inc.

County Stafford 127.53

Name & Address Rt. 1, Box 183B

Well Total Depth 3924' feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase KS, 67524

Company to plug at: Hour: 1:15 p.m. Day: 8 Month: 9 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 3923' Perfs at 3526-3780' Elevation 1906' KB

1st plug sand back to 3475' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:40 p.m. Day: 8 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 3475' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 10 1987 9-10-87

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2920' of 5 1/2 casing. (If additional description is necessary, use BACK of this form.)

(If desired, observe this plugging.)

Signed Dan Gooden (TECHNICIAN)

INVOICED
DATE SEP 11 1987
INV. NO. 18077