

To: 1 052074  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Docket #E-23,836 15-185-20561-0000

E/2 NW NW, SEC. 12, T 22 S, R 14 W/8  
4620 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

10-14

Operator License # 9069  
Operator: General Oil Company, Inc.  
Name: 1540 N. Broadway, Ste. 202  
Address: Wichita, KS 67214

Lease Name Williams Well # 1  
County Stafford 124.47  
Well Total Depth 3830 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well Gas Well Input Well X SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 14 Month: 10 Year: 19 96

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

logs: 4 1/2" at 3830' w/250 sx cement, PBD 3720', Perfs at 2582-3566'

1st plug run tubing to 3400' and spot 30 sx cement.

2nd plug fill hole with gel to 800', perforate at 800' and circulate with cement from 800-0'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4 P.m. Day: 14 Month: 10 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx cement through tubing at 3400'.

Filled hole with gel from 2900-800'.

2nd plug perforated at 800' and fill 4 1/2" X 8 5/8" with cement through tubing from 800-0'.

Pulled tubing and squeezed down 4 1/2" to 400 psi.

Used 297 sx cement from 800-0'.

10-18-98

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I (Name) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 10-21-96

INV. NO. 46759  
10-14