

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-10929-00-00<sup>03</sup>  
Spot: CNESWSW Sec/Twnshp/Rge: 12-22S-14W  
990 feet from S Section Line, 990 feet from W Section Line  
Lease/Unit Name: WILLIAMS Well Number: 3  
County: STAFFORD Total Vertical Depth: 3753 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 1305 E. WATERMAN, SUITE A  
WICHITA, KS 67211

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 802  
Production: Size 5.5 feet: 3752  
Liner: Size \_\_\_\_\_ feet:

\$ 121.97

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2001 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GARY WAGNER Company: ANDERSON ENERGY Phone: (785) 735-9747

Proposed Plugging Method: PUMP 25 SX CMT ON BOTTOM & GEL. PERFORATE AT 810' AND CIRCULATE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/10/2001 11:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 3647'. PERFS AT 3553-60 & 3597-3601'. PUMP 100# HULLS - 25 SX CMT - & 28 SX GEL DISPLACED WITH 24 BBL WATER. PERFORATED 5 1/2" AT 825' WITH 2 SHOTS. PUMPED 170 SX CMT DOWN 5 1/2" CASING CIRCULATING CMT TO SURFACE UP 8 5/8" X 5 1/2" ANNULUS.

INVOICED  
DATE 4-24-01  
NO. 2001061710

RECEIVED 4-23-01  
STATE CORPORATION COMMISSION  
APR 23 2001  
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

APR 20 2001

MD

Form CP-2/3