

1 120547

4-2

API NUMBER 15- 185-22,289-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE NE, SEC. 12, T 22 S, R 14 W/E
4290 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name Roach Well # A-5

Operator: Davis Petroleum, Inc.

County Stafford 126.75

Name & Address RR 1, Box 183 B

Well Total Depth 3900 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 370

Abandoned Oil Well Gas Well Input Well SMD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 8 a.m. Day: 2 Month: 4 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3899' w/190 sx cement, PBSD 3700', Perfs 3519-92' (4 sets), 3788-3802'

1st plug sand back to 3465' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

4-4-91
APR 04 1991

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN) CONSERVATION DIVISION
Wichita, Kansas

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:30 a.m. Day: 2 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3465' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2600' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
Please observe this plugging.

DATE 4-11-91

Signed *Steve Pfeifer*
(TECHNICIAN)

INV. NO. 31468