

1 120455

7-24 15-185-19445-00-01

T&I  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- E-6844

SE NE SW, SEC. 11, T 22 S, R 13 W E  
1650 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7702

Lease Name Sittner Well # 1

Operator: Stalcup Oil Company

County Stafford 123.50

Name & Address 3511 23rd Street

Well Total Depth 3800 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10" feet 239

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well X SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 8 a.m. Day: 24 Month: 7 Year: 1990

Plugging proposal received from Ralph Stalcup

(company name) Stalcup Oil Company (phone) 316-793-3118

were: 5 1/2" at 3798' w/150 sx cement, Perfs at 3390-3575'

1st plug clean hole to 1,000', perforate casing at 720', run tubing to 1000' and pump in 6 sx gel and hulls,

2nd plug pull tubing to 730' and circulate with cement.

Plugging Proposal Received by Duane Rankin  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 24 Month: 7 Year: 1990

ACTUAL PLUGGING REPORT 1st plug cut and pulled 725' of tubing, perforated 5 1/2" casing at 722', ran tubing to 725' and circulated casing and hole with 6 sx gel and hulls and 300 sx cement.

2nd plug pulled tubing and filled casing with 10 sx cement.

7-30-90

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

Signed Duane Rankin  
(TECHNICIAN)

DATE: 8-3-90

INV. NO. 28902

7-24