

To: 1 120707 5-5
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-185.02007-0000 71P
API NUMBER 15- Drilled 4/6/38
SE SE SW, SEC. 11, T. 22 S, R. 13 W/E
330 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7702
Operator: Stalcup Oil Company
Name & Address 3511 23rd St.
Great Bend, KS 67530

* Lease Name Hullman Well # B-1
County Stafford 122.04
Well Total Depth 3755 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 209

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 5 Month: 5 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 6" at 3754' w/175 sx cement, Perfs at 3379'

1st plug sand back to 3330' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 75 sx cement, 10 sx gel, 2 sx hulls, and 175 sx cement.

*This has been called Sittner in recent years.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 5 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 6" casing back to 3320' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped into 10 3/4" surface casing with 300 lbs. hulls, 10 sx gel, 75 sx cement,

10 sx gel, 200 lbs. hulls and 175 sx cement.

Welded plate to 5 1/2" collar on top of 10 3/4" surface casing.

Pumping pressure 0-500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1100' of 6" casing.

(If additional description is necessary, use BACK of this form)

I (did/did not) observe this plugging.

DATE 5-22-92

INV. NO. 35313

Signed Duane Rankin
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
MAY 11 1992
CONSERVATION DIVISION
WICHITA, KANSAS