

1 120904

3-23

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-22,023-0000
150' S & 80' W
N/2 NW SW, SEC. 11, T. 22 S, R. 13 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170
Operator: Globe Operating Inc.
Name:
Address P.O. Box 12
Great Bend, KS 67530

2160 feet from S section line
5000 feet from E section line
Lease Name Sittner Well # 6
County Stafford 129.02
Well Total Depth 3970 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 23 Month: 3 Year: 1994
Plugging proposal received from Ralph Stalcup

(company name) Globe Operating Inc. (phone) 316-792-7607
wells: 5 1/2" at 3969', Perfs at 3768-73'

1st plug sand back to 3700' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 3:30 p.m. Day: 23 Month: 3 Year: 1994

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3700' and dumped 5 sx cement on top
of sand through bailer,
2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-500 psi and shut in 100 psi.

3-28-94

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2400' of 5 1/2" casing. STATE CORPORATION COMMISSION

(if additional description is necessary, use BACK of this form)

INVOICED
DATE 3-30-94
OBSERVE THIS PLUGGING.

DATE 3-30-94
INV. NO. 40198

RECEIVED
MAR 28 1994
Signed _____
(TECHNICIAN) CONSERVATION DIVISION
Wichita, Kansas