

1052307

TO: STATE CORPORATION COMMISSION

4-7

API NUMBER 15-185-21,352-0000
W/2 N/2 SW SE SEC. 11, T 22 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 1260 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 560 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME WITT WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 123.50

OPERATOR LICENSE # 6170

WELL TOTAL DEPTH 3800 FEET

OPERATOR: GLOBE OPERATING, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 3800' WITH 150 SX

NAME AND PO BOX 12

SURFACE CASING: SIZE 8 5/8" @ 300' WITH 300 SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 07 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3402 TOP

SANDED TO 3350' AND 4 SX CEMENT. PUMPED DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8% PLUG - 100 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 07 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED TO 3350' AND 4 SX CEMENT.

PUMPED DOWN 8% WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8% PLUG - 100 SX CEMENT.

MAXIMUM PRESSURE AT 800 PSIG.

SHUT IN PRESSURE AT 400 PSIG.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2615' OF 4 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

DO NOT OBSERVE THIS PLUGGING.

RECEIVED

SIGNED

Richard M. Lacey (TECHNICIAN)

FORM CP-2/3

DATE APR 16 1999

APR 13 1999

INV. NO. 60849

CONSERVATION DIVISION Wichita, Kansas

4-13-99