

To: 1 052125 4-15 API NUMBER 15- 6/5/66 Spud Date 15-185-30311-0000

STATE, CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION 40' W SE SE NW, SEC. 10, T. 22 S, R. 13 W XX

133 S. Market, Room 2078
Wichita, KS 67202
2970 feet from S section line
3010 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 7702 Lease Name Hullman Well # 2

Operator: Stalcup Oil Company County Stafford 124.64

Name: 3218 N. Main, Ste. 7 Well Total Depth 3835 feet

Address: Great Bend, KS 67530 Conductor Pipe: Size feet

Surface Casing: Size 8.5/8 feet 283

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 15 Month: 4 Year: 19 97

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 5 1/2" at 3834', Perfs at 3441-45, 3544-47'

1st plug sand back to 3390' and dump 5 sx cement on top of sand through bailer,

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.

hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 15 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT

1st plug sanded back to 3990' and dumped 5 sx cement on top of sand

through bailer,

Spotted plugs through 5 1/2" casing: 4-24-97

2nd plug at 800' with 10 sx gel and 50 sx cement,

3rd plug at 300', circulated with 100 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1920' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE 4-28-97
INV. NO. 48076
Signed Richard W. Lacey (TECHNICIAN)

RECEIVED
KANSAS
CORP
APR 24 4 11 PM '97