

TO: 1052224

API NUMBER 15-185-21,538-0000
100' W of
NE NW SW, SEC. 10, T 22 S, R 13 W

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION

2-9 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

4390 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME Hullman WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY Stafford 124.80

OPERATOR LICENSE # 32017

WELL TOTAL DEPTH 3840 FEET

OPERATOR: ABC Oil & Salvage

PRODUCTION CSG: SIZE 4 1/2" FEET 3831w/200 sx

NAME AND RR #3, Box 151

SURFACE CASING: SIZE 8 5/8" FEET 305

ADDRESS Lyons, KS 67554

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Quality Well Service, Inc. LICENSE NUMBER 31925

ADDRESS 249 Beth Dr., Sterling, KS

COMPANY TO PLUG AT: HOUR: 8 a.m. DAY: 9 MONTH: 2 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Richard McIntyre

(COMPANY NAME) Quality Well Service, Inc. (PHONE) 316-727-3410

WERE: Perfs at 3790-3810'

1st plug sand back to 3709' and dump 4 sx cement on top of sand through bailer,

2nd plug at 900' w/10 sx gel and 50 sx cement,

3rd plug at 340' with 50 sx cement,

4th plug at 40' with 10 sx cement.

PLUGGING PROPOSAL RECEIVED BY Richard Lacey

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 a.m. DAY: 9 MONTH: 2 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 3709' and dumped 4 sx cement on top of sand through bailer,

Pumped plugs through casing:

2nd plug at 900' with 10 sx gel, 50 sx cement and 5 sx gel,

3rd plug at 340' with 50 sx cement,

4th plug at 40' with 10 sx cement.

REMARKS: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2021' of 4 1/2" casing.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE FEB 17 1998

SIGNED Richard W. Lacey
(TECHNICIAN) FORM CP-2/3

INV. NO. 50079

2-9

RECEIVED
DATE 2-13-98
FEB 15 1998