

1 080499

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,572-0000

NW NW NW, SEC. 10, T. 22 S, R. 13 W XX

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Hulliman Well # 1

Operator: Landmark Oil Exploration, Inc.
Name &
Address 105 South Broadway, Suite 1040
Wichita, KS 67202

County Stafford 122.95

Well Total Depth 3783 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 374

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:00 pm Day: 21 Month: March Year: 19 86

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3370' PBTB 3773' Perfs at 3412-43'; 3504-20'; 3637-75'; 3720-78'

1st plug sand back to 3370' and dump 5' sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 pm Day: 21 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement at 3400' 2000' shut in.

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 325 psi

Remarks: Recovered 2540' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did ~~XXXXXX~~ observe this plugging.

STATE CORPORATION COMMISSION

Signed J. H. [Signature]
(TECHNICIAN)

DATE APR 1 1986

MAR 31 1985

INV. NO. 13232

CONSERVATION DIVISION
Wichita, Kansas

3-31-86