

To: 1 052150 7-28
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Drilled 1957
SW SE NW, SEC. 10, T 22 S, R 13 W/E
2970 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7702
Operator: Stalcup Oil Company
Name & Address: 3218 N. Main, Ste. 7
Great Bend, KS 67530

Lease Name: Hullman Well # 1
County: Stafford 122.72
Well Total Depth: 3776 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor: D S & W Well Servicing, Inc. License Number: 6901
Address: P.O. Box 231, Claflin, KS 67525-0231

Company to plug at: Hour: 1 p.m. Day: 28 Month: 7 Year: 1997

Plugging proposal received from: Ralph Stalcup
(company name) Stalcup Oil Company (phone) 316-793-3118

Logs: 5 1/2" at 3770', Perfs at 3503-06, 3517-22, 3584-87'
Casing collapsed at 900' and completely eaten up to surface

Perforate at 800', run tubing and fill with cement. 8-4-97

Plugging Proposal Received by: Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 28 Month: 7 Year: 1997

ACTUAL PLUGGING REPORT Perforated 5 1/2" at 800', ran tubing to 760'.

1st plug pumped 5 sx gel and 220 sx cement. Good circulation, no cement. Waited on cement two hours, tagged cement at 420'.

2nd plug pulled tubing to 360', circulated cement up 8 5/8" X 5 1/2" with 95 sx.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

1 (did / observe this plugging.

Signed: Richard W. Lacey (TECHNICIAN)

INVOICED
DATE 8-5-97
INV. NO. 48720

7-28 OCT 30 1997