

1 080472

15-185-11204-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- N/A

NW SW SW , SEC. 6 , T 22 S, R 13 W/X

990 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5153

Lease Name Schmid Well # 4

Operator: Texaco, Inc.

County Stafford 120.77

Name & Address P. O. Box 2420

Well Total Depth 3716 feet

Tulsa, OK 74102

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 576

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901

Address P. O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9:00 am Day: 9 Month: January Year: 19 86

Plugging proposal received from Jim Parkhurst

(Company name) Texaco, Inc. (phone) 316-298-2031

were: 5 1/2" at 3704' Open Hole 3704-3716 Spot through tubing with mud between plugs

1st plug spot 30 sx cement through tubing at 3714'

2nd plug at 2487' with 15 sx cement

3rd plug at 905' with 100 sx cement to circulate

4th plug pump 85 sx cement down 8 5/8"

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:30 pm Day: 9 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug spotted 30 sx cement through tubing at 3714', 2nd plug

at 2487' with 15 sx cement, 3rd plug at 905' with 100 sx cement - cement circulated.

4th plug pumped 85 sx cement down 8 5/8"

STATE CORPORATION COMMISSION

1-27-86 JAN 27 1986

Maximum pressure 600 psi and shut in 250 psi

CONSERVATION DIVISION

Remarks: no recovery. Used Class A 3% cc by BJ-Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If applicable) observe this plugging.

DATE FEB 5 1986

Signed J. H. Metz (TECHNICIAN)

INV. NO. 12377