

4-070971

11-25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-24,499 0000  
150'S. & 100'W.  
NE NW SE /4 SEC. 04, 16 S, 12 W  
2160 feet from S section line  
1800 feet from E section line

Operator license# 6039

Lease John Miller well # 1

Operator: L.D. Drilling, Inc.

County Barton

109.20

Address: R.R. #1  
Box 183B  
Great Bend, Kansas 67530

Well total depth 3360 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 419 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: L.D. Drilling, Inc. License# -

Address: R.R. #1 - Box 183B - Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 25 Month: November Year: 91

Plugging proposal received from: Greg Davidson - L.D. Davis

Company: L.D. Davis Drilling Phone: 316-793-3051

Were: 8 5/8" - 419' S.P. cwc. w/200 sx. 65/35 pozmix - 6% gel. -  
3% c.c. by Halliburton Conglomerate Well. Elv. 1882' - Anhy. 805' -  
No cir. problems. 44 vis. - 8.7 wt. Proposal 185 sx. 60/40 pozmix -  
6% gel. - 3% c.c. Spot with drill stem, circulate, heavy mud between  
all plugs. 25 sx. @ 3240' - 70 sx. @ 480' - 25 sx. @ 810' -  
40 sx. @ 180' - 10 sx. @ 40'. 15 sx. in Rathole - circulate.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:15A.M. Day: 25 Month: November Year: 91

Actual plugging report: L.D. Drilling ordered 160 sx. 60/40 pozmix -  
6% gel. - 3% c.c. Spotted with drill stem, circulated hole. Heavy mud  
between all plugs (operator did not find arbuckle.)

25 sx. cement @ 810'.  
70 sx. cement @ 480'.  
40 sx. cement @ 180'.  
10 sx. cement @ 40'.  
15 sx. Rathole (Circulate)

RECEIVED  
STATE CORPORATION COMMISSION

12-12-91 DEC 12 1991

Remarks: \_\_\_\_\_

Conservation Division  
Wichita, Kansas

I have  did not  observe the plugging.

**INVOICED**  
DATE DEC 12 1991  
INV. NO. 34189

*John S.*

*Marion J. Schmidt*  
(agent)

FOR KCC USE:

EFFECTIVE DATE: 11-18-91

DISTRICT # 4

SEAT... Yes... No

BARTON 499

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

NOTICE OF INTENT TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date November 25 1991

Spot 150' S and 100' W NE-NW-SE Sec 4 Twp 16. S, Rg 12. X East West

2160 feet from South North line of Section 1800 feet from East West line of Section IS SECTION X REGULAR IRREGULAR?

OPERATOR: License # 6039 Name: L. D. DRILLING, INC. Address: R.R. 1 BOX 183 B City/State/Zip: Great Bend, Ks. 67530 Contact Person: L. D. Davis Phone: (316) 793-3051

(NOTE: Locate well on the Section Plat on Reverse Side) County: BARTON

Lease Name: John Miller Well #: 1 Field Name: Beaver North

CONTRACTOR: License #: 6039 Name: L. D. Drilling, Inc.

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Arbuckle Nearest lease or unit boundary: 450'

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec X Infield X Mud Rotary Gas Storage Pool Ext. Air Rotary OWD Disposal Wildcat Cable Seismic: # of Holes Other

Ground Surface Elevation: 1877 feet MSL Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no Depth to bottom of fresh water: 260'

Depth to bottom of usable water: 380' Surface Pipe by Alternate: X 1 2

If OWD: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Length of Surface Pipe Planned to be set: 400'

Length of Conductor pipe required: none Projected Total Depth: 3400'

Formation at Total Depth: Arbuckle Water Source for Drilling Operations:

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location:

... well ... farm pond X other DWR Permit #: trucked - city or farm pond

Will Cores Be Taken? yes X no If yes, proposed zone:

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

- 1. Notify the appropriate district office prior to spudding of well; 2. A copy of the approved notice of intent to drill shall be posted on each drilling rig; 3. The minimum amount of surface pipe as specified below shall be set by circulating cement to the top; in all cases surface pipe shall be set through all unconsolidated materials plus a minimum of 20 feet into the underlying formation; 4. If the well is dry hole, an agreement between the operator and the district office on plug length and placement is necessary prior to plugging; 5. The appropriate district office will be notified before well is either plugged or production casing is cemented in; 6. IF AN ALTERNATE II COMPLETION, PRODUCTION PIPE SHALL BE CEMENTED FROM BELOW ANY USABLE WATER TO SURFACE WITHIN 120 DAYS OF SPUD DATE. IN ALL CASES, NOTIFY DISTRICT OFFICE PRIOR TO ANY CEMENTING.

I hereby certify that the statements made herein are true and to the best of my knowledge and belief. Date: Nov. 11, 1991 Signature of Operator or Agent: L. D. Davis Title: President

4109 Division 11-18-91

FOR KCC USE: API # 15-009-24,499 Conductor pipe required 200 feet Minimum surface pipe required 400 feet per Alt 1 Approved by: [Signature] 11-13-91 This authorization expires: 5-13-92 (This authorization void if drilling not started within 6 months of effective date.) Spud date: 11-14-91 Agent: [Signature]

NOV 13 1991 [Signature]

RECEIVED STATE CORPORATION COMMISSION

DEC 12 1991

REMEMBER TO:

- File Well Pit Application (form CDP-1) with Intent to Drill; - File Completion Form ACO-1 within 120 days of spud date; - File acreage attribution plat according to field proration orders; - Notify appropriate district office 48 hours prior to workover or re-entry; - Submit plugging report (CP-4) after plugging is completed; - Obtain written approval before disposing or injecting salt water.

Mail to: Conservation Division, 200 Colorado Derby Building, 202 W. First St., Wichita, Kansas 67202-1286.

NOV 14 1991

4 16 1280