

4-061014

12-10

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-24,499-0001

NE NW SE /4 SEC. 04, 16 S, 12 W
2160 feet from S section line
1800 feet from E section line

Operator license# 31560

Lease Miller OWWO Well # 1

Operator: Maxwell Operating Company, Inc.

County: Barton

Address: 1675 Broadway - Suite #1060
Denver, Colorado 80202

Well total depth 3360 109.20 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 419 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address: Hays, Kansas 67601

Company to plug at: Hour: 4:00 P.M. Day: 10 Month: December Year: 1996

Plugging proposal received from: Tom Alm

Company: Discovery Drilling, Inc.

Phone:

Were: Order 130 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.

Space all plugs with heavy drilling mud through drill pipe.

Drilled down during OWWO and got out of hole. Drilled down to conglomerate,
tested and decided to plug and abandon.

TD in conglomerate.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 6:30 P.M. Day: 10, Month: December Year: 1996

Actual plugging report:

1st. Plug at 800' w/25 sxs. Anhydrite 805' - 825'. 12-23-96

2nd. Plug at 500' w/80 sxs. Dakota into surface pipe at 419'.

3rd. Plug at 40' w/10 sxs.

Rathole with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO X Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 1882 GL

and []/aid not [X] observe the plugging.

INVOICED

JAN 03 1997

DATE

INV. NO. 47233

FEB 17 1997

12-10

(agent)

Form CP-2/3