

15-185-19417-0001

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER comp. 6-24-60

LEASE NAME Ward

WELL NUMBER "B" #1 WWD

SPOT LOCATION NE NW SE

SEC. 15 TWP. 23 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 6-24-60

Plugging Commenced 4-5-84

Plugging Completed 5-4-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum Inc.

ADDRESS Box 1447, Great Bend, Kansas 67530

PHONE # (316)-793-8968 OPERATORS LICENSE NO. 5238

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? 1

Is ACO-1 filed? Yes If not, is well log attached? With application

Producing formation Arb. Disposal Depth to top 3813 bottom 3818 T.D. 3818'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	250'	None
				5-1/2"	3816'	2,544.37"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3760' and 10 sacks cement. Shot casing at 3200', 3000', 2750', 2500'. Pulled 78 joints of 5-1/2" casing. Squeezed well with 3 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 100 sacks 50/40 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 900 psi and shut in 250 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Great Bend, Ks.

SUBSCRIBED AND SWORN TO before me this 17th day of May, 1984

STATE
NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

5-10-84
MAY 10 1984

My Commission expires: Wichita, Kansas