

15-185-12439-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 15 Twp. 23S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW

Lease Owner Tennessee Gas Transmission Company

Lease Name W. Dayle Aitken Well No. 1

Office Address P. O. Box 513, Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-20 1956

Application for plugging filed 9-21 1956

Application for plugging approved 9-20 Oral 1956

Plugging commenced 9-20 1956

Plugging completed 9-20 1956

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3870 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8" OD	271'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud from TD to 210'

Set HOWCO Plug at 210'.

1/3 sack of hulls and 20 sacks cement on top of plug.

Set Second HOWCO Plug at 40'.

1/3 sack of hulls and 10 sacks cement on top of second plug

to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Group Exploration Company

Address Sterling, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.

Glen E. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address) _____

Subscribed and Sworn to before me this 21 day of September, 1956

My commission expires May 20, 1958 Vincent O. Gray Notary Public.

PLUGGING
FILE SEC 15 T 23 R 13W
BOOK PAGE 101 LINE 21

9-25-56

GROUP EXPLORATION COMPANY
Sterling, Kansas

15-185-12439-0000

WELL LOG-----AITKEN #1

Location: SE SE NW, Section 15-23S-13W,
Stafford County, Kansas

OWNER: Tennessee Gas Transmission Company
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: 9-6-56 (w.r.)
COMPLETED: 9-20-56 (w.r.)

TOTAL DEPTH: 3870'

LOG

CASING RECORD

0-160	Sand	
160-271	Shale	
271-560	Shale & Red Bed	
560-765	Red Bed	
765-805	Anhydrite	
805-1150	Shale & Limestone	
1150-1465	Shale & Shells	
1465-1850	Limestone & Shale	
1850-2115	Limestone	
2115-2730	Shale & Limestone	
2730-2935	Shale	
2935-3380	Limestone & Shale	
3380-3414	Shale	
3414-3770	Limestone	
3770-3799	Cherty Limestone	
3799-3822	Shale & Limestone	
3822-3870	Arbuckle Limestone	T.D.

Set 8-5/8" casing at 270' with 275
sacks cement, 3 sacks calcium chloride.

PRODUCTION

Plugged & Abandoned

PLUGGING
FILE SEC. 15 T. 23 R. 13W
BOOK PAGE 101 LINE 21

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 X 1956
CONSERVATION DIVISION
Wichita, Kansas