

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-185-00694-0060

API NUMBER comp. 7-27-56

LEASE NAME Ward

WELL NUMBER #2

SPOT LOCATION SW SW NE

SEC. 15 TWP 23 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 7-27-56

Plugging Commenced 3-27-84

Plugging Completed 5-4-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Petroleum, Inc.

ADDRESS Box 1447, Great Bend, Kansas 67530

PHONE # (316) 793-8968 OPERATORS LICENSE NO. 5238

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One

Is ACO-1 filed? Yes If not, is well log attached? With application

Producing formation Arb, Simp., Lans. Depth to top 3411 bottom 3810 T.D. 3818'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	267'	None
				5-1/2"	3813'	1,658.51'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3400' and 5 sacks cement. Shot casing at 3000', 2800', 2500', 2300', 2000' and 1630'. Pulled 52 joints of 5-1/2" casing. Squeezed well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 100 sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 500 psi and shut in was zero.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold
James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

RECEIVED
STATE CORPORATION COMMISSION

5-10-84

MAY 10 1984

SUBSCRIBED AND SWORN TO before me this 10th day of May, 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires:

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-87

Iona M. Leatherman
Notary Public