

15-185-00042-0000

WELL PLUGGING RECORD

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 211 No. Broadway Wichita, Kansas

Stafford County. Sec. 15 Twp. 23 Rge. 13 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines. NE SW NE

Lease Owner Petroleum, Inc.

Lease Name Ward Well No. 1

Office Address Route 2, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed May 5, 19 52

Application for plugging filed September 27, 19 57

Application for plugging approved September 30, 19 57

Plugging commenced October 2, 19 57

Plugging completed October 10, 19 57

Reason for abandonment of well or producing formation

Depletion of producible zones

If a producing well is abandoned, date of last production April 14, 19 56

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R.M. Brundage, Hoisington, Kansas

Producing formation Arbuckle Depth to top 3808' Bottom ---- Total Depth of Well 3819 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Rows include Arbuckle and Kansas City formations.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

(Plugged back to 3452')

Filled hole with crushed rock from 3452' to 3449' and placed 6 sacks cement on top of rock. Mudded up to 250' and made solid rock bridge on top of mud. Placed 25 sacks cement on top of rock bridge and mudded up to 35'. Made solid rock bridge at 35' and filled hole to base of well cellar with 10 sacks cement.

RECEIVED

OCT 19 1957

10-19-57

CONSERVATION DIVISION Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Morgan Well Plugging Service

Address 102 West 18th Street, Hutchinson, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Don Searle (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

Route 2, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of October, 19 57

Notary Public signature

My commission expires July 11, 1960

PLUGGING FILE SEC 15 T. 23 R. 13W BOOK PAGE 49 LI E 15

15-185-60042-000

DRILLER'S LOG WARD NO. 1

Petroleum, Inc. and Stanolind Oil & Gas Company, Lease Owners

Section 15, Twp. 23S, Rge. 13W

Garvey Drilling Company, Contractor

Location: NE SW NE

Drilling Commenced: April 6, 1952
Drilling Completed: April 18, 1952

County: Stafford County, Kansas

Production: Arbuckle

Casing Record: 8 5/8" @ 255' w/174 sax
5 1/2" @ 3810' w/75 sax

R.T.D.: 3819'

Figures below indicate bottom of formation:

270	Surface shale
760	Red Bed
800	Anhydrite
1755	Shale & Shells
1865	Lime, Shale & Shells
2110	Lime & Shale
3215	Lime
2535	Shale & Lime
2900	Shale & Shells
3200	Lime & Shale
3230	Lime
3435	Lime & Shale
3720	Lime
3724	Lime & Shale
3762	Cherty Lime
3810	Shale
3819	Lime
3819'	R.T.D.

Tops:

Heebner:	3276 (-1394)
Brown Lime:	3411 (-1529)
Lansing:	3428 (-1546)
Viola:	3724 (-1842)
Simpson:	3760 (-1878)
Arbuckle:	3808 (-1926)

DST #1, 3512-25, open 1 hr., rec. 30' oil cut mud, 0# BHP.
 DST #2, 3810-15, open 30 mins., rec. 10' mud, 0# BHP.
 DST #3, 3811-19, open 1 hr., rec. 270' free oil plug 120' muddy oil, 1250# BHP.

I hereby certify that this is a true and correct log of the above mentioned well.

NOTARY PUBLIC
 OCT 12 1957
 COUNTY OF SEDGWICK
 DIVISION
 Kansas
 SS:

PETROLEUM, INC.

BY W.W. Fisher
W. W. Fisher

STATE OF KANSAS
COUNTY OF SEDGWICK

PLUGGING	
FILE SEC	15 T. 23 R. 13W
BOOK PAGE	49 LINE 15

Subscribed to and sworn to before me, a Notary Public in said County and State, this 28th day of April, 1952.

Charlotte Haseman
Notary Public

My commission expires: October 13, 1954.