


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County, Sec. 16 Twp. 23S Rge. 13 ~~XXX~~ (W)

Location as "NE/CNW&SW" or footage from lines SE SE SW
Lease Owner D. R. Lauck Oil Company, Inc.
Lease Name Schulz Well No. B-1
Office Address 301 So. Broadway, Wichita 2 Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed July 15 19 55
Application for plugging filed July 15 19 55
Application for plugging approved July 15 19 55
Plugging commenced July 15 19 55
Plugging completed July 15 19 55
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production --- 19 ---
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3945 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|-----|--------|--------|------------|
| | | 0 | 162 | 8 5/8" | 162' | none |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

hole filled with mud - wood plug put in casing and 100 sacks of cement pumped on top of plug;

mud 3945 - 310' approx.
plug 310 - 306
cement 306 - 6' bottom of cellar

RECEIVED
JUL 21 1955
CONSERVATION DIVISION
WICHITA, KANSAS
7-21-55

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Globe Oil Well Cementing Co.
Address Great Bend Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
John H. Knightley (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19 day of July, 19 55

My commission expires Sept. 14, 1955

Elizabeth Gay
Notary Public.

PLUGGING
FILED SEC 16 T 23 R 13W
BOOK PAGE 135 LINE 24

PLUGGING
FILED SEC 16 T 23 R 13W
BOOK PAGE 135 LINE 24

D. R. Lauck Oil Company, Inc.

15-185-00672-0000

Schulz B-1

SE SE SW Sec. 16-23S- 13W
Stafford County Kansas

Commenced: July 2, 1955
Completed July 15, 1955

RTD 3945 Casing: 162' 8 5/8" cemented w/165 sacks

Elevation: GR 1876; DF 1878; KB 1880

Tops

| | |
|------------------------|------|
| Sand | 70 |
| shale & shells | 205 |
| sand | 280 |
| red bed & sand | 755 |
| Anhydrite | 780 |
| red bed-shale & shells | 940 |
| red bed-shale | 1025 |
| salt & shale | 1115 |
| lime & shale | 1375 |
| shale & shells | 1600 |
| shale & lime | 2130 |
| broken lime | 2275 |
| lime & shale | 2380 |
| shale | 2415 |
| lime & shale | 2540 |
| shale & shells | 2810 |
| lime & shale | 3267 |
| Lime | 3277 |
| lime & shale | 3458 |
| Lime | 3708 |
| Lime & shale | 3775 |
| Lime | 3945 |

| | Sample | Halliburton |
|--------------------|-------------|-------------|
| Anhydrite | 755 pl 1125 | |
| Heebner | 3314-1434 | 3313-1433 |
| Brown lime | 3449-1569 | 3448-1568 |
| Lansing | 3470-1590 | 3470-1590 |
| Base K.C. | 3720-1840 | 3724-1844 |
| Marmaton Chert | 3737-1857 | 3730-1850 |
| Viola | 3807-1927 | 3810-1930 |
| Simpson | 3843-1963 | 3851-1971 |
| Arbuckle | 3904-2024 | 3903-2023 |
| Rotary Total Depth | 3945-2065 | |

DST #1 3493-3520 weak blow; 7 min.;
open 20 min. rec. 15' mud;
BHP 1140# in 20 min.

DST #2 3652-3670 weak blow for 40";
open 1 hour; rec. 30' mud
with specks of oil;
BHP 98# in 20 min.

RTD 3945

D & A.

REC
STR

GEN

PLUGGING
 FELX SEC-16 T-23 R-13W
 BOOK PAGE 135 LINE 24