

15-185-30263-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plot

Stafford County. Sec. 18 Twp. 23S Rge. 13 (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines. SE SW SW
Lease Owner Sterling Drilling Company
Lease Name Gray Well No. 4
Office Address Box 127, Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 1 19 66
Application for plugging filed June 30 19 66
Application for plugging approved June 30 19 66
Plugging commenced 11:45 p.m., June 30, 19 66
Plugging completed 4:00 a.m., July 1, 19 66
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3680 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Casing	0	379	7"	X	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 300', bridge and Halliburton plug at 300', 20 sacks cement thru drill pipe. Filled hole with heavy mud to 40', bridge and Halliburton plug at 40', 8 sacks cement to base cellar. Bridge at 7' in rat hole and 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 8 1966

7-8-66

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address Box 127, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
Box 127, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of July, 19 66

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

My commission expires BERNARD LAUDERMILK, Notary Public
Commission Expires January 22, 1970

15-185-30263-0000

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- GRAY #4

LOCATED: SE SW SW Section 18-23S-13W, Stafford County, Kansas

OWNER: Sterling Drilling Company, et al
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: June 23, 1966
COMPLETED: July 1, 1966

ROTARY TOTAL DEPTH: 3680'

LOG

CASING RECORD

0 - 150	Sand & Shale
150 - 325	Shale, Shells & Sand
325 - 1050	Shale & Shells
1050 - 1982	Shale & Lime
1982 - 2420	Lime
2420 - 3375	Lime & Shale
3375 - 3510	Sand, Shale & Lime
3510 - 3635	Lime
3635 - 3680	Lime & Shale T.D.

Ran 12 joints 7" OD casing, 367' pipe set at 379' K.B. with 160 sacks HA-5. Plug was down at 2:45 a.m.

Plugging orders given by Archie Elving, Pratt, Kansas. 20 sacks cement thru drill pipe by Halliburton at 3675'. Heavy mud up to 300', Bridge and Halliburton plug at 300', 20 sacks cement thru drill pipe. Heavy mud to 40', Bridge and Halliburton plug at 40', 8 sacks cement to base cellar. Bridge at 7' in rat hole and 2 sacks cement. Started cementing bottom at 11:45 p.m. 6-30-66, finish top plug and rat hole at 4:00 a.m. 7-1-66.