

15-185-10950-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 18 Twp. 23 Rge. 3 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner Sterling Drilling Company
Lease Name Gray #2 Well No.
Office Address Sterling, Kansas 67579
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9/7/71 19
Plugging completed 9/15/71 19
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation Depth to top Bottom Total Depth of Well 3990 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	368	none
				5 1/2"	3989'	2010'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3680', ran sand to 3600' and dumped 5 sacks of cement.
Shot pipe at 3010', 2890', 2766', 2642', 2522', 2429', 2335', 2215',
2100', 2007', worked pipe loose and pulled 67 joints. Allied squeezed
well with 2 sacks hulls, 75 sacks gel and 100 sacks cement.

PLUGGING COMPLETE.

*Reed
8-26-71*

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 71



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

COPY


15-185-10950-0000

Company. STERLING DRILLING CO.
Farm. Gray No. 2

SEC. 18 T. 23 R. 13W
NW SW SW

Total Depth. 3990'
Comm. 3-10-56 Comp. 4-7-56
Shot or Treated.
Contractor. Sterling Drlg. Co.
Issued. 6-16-56

County Stafford
KANSAS



Elevation. 1911' RB

Production. 125 BOFD

CASING:

8 5/8" 368' cem w/225 sx
5 1/2" 3989' cem w/150 sx

Figures indicate bottom of Formations.

sand and shale	375
red bed & sand	805
anhydrite	825
red bed & shale	1100
shale & shells	1465
shale	1755
shale & limestone	1915
limestone	2010
limestone & shale	2620
shale & shells	2785
shale & limestone	3130
limestone	3325
shale & limestone	3525
limestone	3780
Conglomerate, limestone & shale	3840
limestone	3915
Simpson.	3960
Arbuckle limestone	3990
Total Depth	

Tops: Scout	
Haebner	3345
Kansas City	3500
Viola	3845
Arbuckle	3960

Perforated 3661-67 with 4 shots per foot.
Reconented production casing with 100 sacks.
Squeezed with 100 sacks pozmix. Perforated
3661-65 with 4 shots per foot. Acidized with
1000 gal. Swabbed 6 BFPH Set plug at 3650'
and perforated 3618-26 with 4 shots per foot.
Acidized with 1500 gal. POP

Drilled Deeper 3-12-56 for S.W.D.
Arbuckle 3990-4009 T.D.

RECEIVED
STATE CORPORATION COMMISSION
AUG 26 1971
CONSERVATION DIVISION
Wichita, Kansas