


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 18 Twp. 23S Rge. 13W (E) (W)  
Location as "NE/CNW%SW%" or footage from lines App. NE SE SE  
Lease Owner Buick Drilling Inc. - et al  
Lease Name French Well No. 1  
Office Address P. O. Box 331 - St. John, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 9, 1957  
Application for plugging filed January 9, 1957  
Application for plugging approved January 9, 1957  
Plugging commenced January 9, 1957  
Plugging completed January 9, 1957  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	210'	8 5/8"	210'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From 4,000' back to 180' with heavy rotary mud placed through drill pipe. Set solid plug 8 ft. long, and 1/2 bbl. of rock. Top of bridge at 195'. 25 sacks cement placed through drill pipe. Gel mud to 35' and 1/3 sacks hulls. Set plug and 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Buick Drilling Inc.  
Address P. O. Box 331 - St. John, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.  
H. R. Buick (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
P. O. Box 331 - St. John, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 57

My commission expires December 26, 1959

[Signature] Notary Public.  
**RECEIVED**  
STATE CORPORATION COMMISSION  
JAN 14 1957 1-14-57  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 18 T 23 R 13 W  
BOOK PAGE 133 LINE 1

DRILLERS LOG

15-185-00705-0000


French #1  
 Commenced R.D.: 12-20-56  
 Completed R.D.: 1-8-57  
 Total Depth: 4,000'  
 Casing record: 210' of 8 5/8"

App. NE SE SE, Sec. 18-23S-13W  
 Stafford County, Kansas  
 Elevation: 1909 D.F.  
 Initial Prod: Lansing-Kansas City  
 Contractor: Buick Drilling Inc.

STRATA	DEPTH
Surface clay	0 - 30
Sand and gravel	30 - 70
Yellow clay	70 - 120
Blue Shale	120 - 247
Dakota sand	247 - 320
Red bed and fine sand	320 - 420
Red bed and coarse sand	420 - 625
Red bed	625 - 650
Sand	650 - 685
Shaley sand	685 - 803
Anhydrite	803 - 845
Shale and shells	845 - 1270
Salt and shale	1270 - 1400
Shale and shells	1400 - 1700
Lime and shale	1700 - 3705
Lime	3705 - 3730
Lime and shale	3730 - 3983
Lime	3983 - 4000 T.D.

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.



H. R. Buick, President

Signed and sworn to in my presence this 10th day of January, 1957, by H. R. Buick, President of the Buick Drilling Inc.



Notary Public

My commission expires: December 26, 1959.

PLUGGING  
 FILE SEC. 18 T. 23 R. 13W  
 BOOK PAGE 123 LINE 1

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 14 1957

CONSERVATION DIVISION  
 Wichita, Kansas