

15-185-11574-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 21 Twp. 23 Rge. 13 (X) W (W)

Location as "NE/CNW/SW" or footage from lines SW NW SW

Lease Owner White Eagle Oil Company

Lease Name Francis Well No. 1

Office Address First National Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 30 19 53

Application for plugging filed September 30 19 53


Application for plugging approved September 30 19 53

Plugging commenced September 30 19 53

Plugging completed September 30 19 53

Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3935 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	326	8 5/8"	326'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from total depth to 270 ft. set bottom plug at 270' with 20 sx cement. Top plug set at 40' and cemented to surface with 10 sx cement.

10-6-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hilton Drilling Company, Inc.
Address P. O. Box 108, Great Bend, Kansas


STATE OF KANSAS, COUNTY OF BARTON, ss.
Henry Peacock, Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock
P. O. Box 108, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 19 53

Margaret Whitmore
Notary Public.

My commission expires April 4, 1956



D R I L L E R ' S L O G

15-185-11574-0000

COMPANY: WHITE EAGLE OIL COMPANY
CONTRACTOR: HILTON DRILLING COMPANY, INC.
FARM NAME: FRANCIS NO. 1
COMMENCED: 9-17-53
COMPLETED: 9-30-53

LOCATION: SW NW SW 21-23-13
Stafford County, Kans.
ELEVATION: 1886 DF

Casing Used: 8 5/8" @ 326' w/250 sx.

Surface Hole	50
Sand	120
Blue and Gray Shale	327
Red Bed Shale	765
Anhydrite	790
Red Rock and Shale	1065
Shale And Shells	1575
Lime and Shale	1720
Brown Lime	1990
Shale and Shells	2015
Lime and Shale	3183
Lime	3390
Shale	3458
Shale and Lime	3733
Lime	3525
Shale and Lime	3789
Conglomerate	3820
Viola Lime and Chert	3832
Lime and Chert	3865
Shale and Lime	3903
Arbuckle Lime	3935
Total Depth	3935

TOPS:

Heebner	3321
Brown Lime	3456
Kansas City	3477
Viola Lime	3805
Simpson Shale	3859
Arbuckle	3909

RECEIVED
REGISTRATION COMMISSION

NOV - 6 1953

MISSION

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

HILTON DRILLING COMPANY, INC.

PLUGGING
FILE SEC 21 T 23 R 13W
BOOK PAGE 133 LINE 12

Henry Peacock
Henry Peacock, Secretary

Subscribed and sworn to before me this 30th day of September, 1953.

My commission expires 4-4-56.

Margaret Whitman
Notary Public