

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail of Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

NORTH


Locate well correctly on above  
Section Plat

Stafford County. Sec. 21 Twp. 23 Rge. 13 (E) W(W)  
 Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SE SE  
 Lease Owner Crown Oil Company, Inc.  
 Lease Name Firebaugh Well No. 1  
 Office Address Odell at Tenth Street, Great Bend, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed December 27 19 49  
 Application for plugging filed December 26 19 49  
 Application for plugging approved December 26 19 49  
 Plugging commenced December 27 19 49  
 Plugging completed December 27 19 49  
 Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was com-  
 menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
 Producing formation Depth to top Bottom Total Depth of Well Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4085' to 326' Heavy Rotary Mud  
 326' plugged with 15 sacks Portland Cement  
 326' to 40' Heavy Rotary Mud  
 40' to Top plugged with 10 sacks Portland Cement

RECORDED

DEC 30 1949 12-30-49

STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Crown Oil Company, Inc., Kansas  
 Address Box 164, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
 H. R. Buick, Drilling Superintendent (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
 described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Buick  
 Crown Oil Company, Inc., Great Bend, Kansas  
 (Address)

SUBSCRIBED AND SWORN to before me this 29th day of December, 19 49

Edwina Elder  
 Notary Public.

My commission expires September 21, 1953.

PLUGGING  
 FILE SEC 21 T 23 R 13W  
 BOOK PAGE 131 LINE 45

15-185-00788-0000

DRILLER'S LOG

COMPANY: CROWN OIL COMPANY, INC.  
CONTRACTOR: HILTON DRILLING COMPANY, INC.  
FARM NAME: FIREBAUGH NO. 1  
COMMENCED: 12-10-49  
COMPLETED: 12-27-49

LOCATION: SE SE SE 21-23-13W  
Stafford County, Kansas  
ELEVATION: 1890 DF

CASING USED: 8-5/8" at 326' with 225 sacks and 2 sacks CC

Sand and Clay	100
Grey Shale and Shells	220
Red Bed	326
Red Bed	560
Red Bed, Shale and Shells	762
Anhydrite	790
Shale and Shells	960
Shale and Shells	1690
Lime and Shale	2010
Lime and Shale Streaks	2095
Lime and Shale	3105
Lime	3200
Lime and Shale	3305
Lime	3460
Lime and Shale	3510
Lime	3801
Lime and Shale	3833
Lime	3865
Cherty Conglomerate	3943
Chert and Lime	3961
Chert	4002
Cherty Conglomerate	4022
Cherty Conglomerate and Shale	4047
Conglomerate and Shale	4068
Lime	4085
Total Depth	4085

GEOLOGICAL TOPS:

Heebner	3336
Lansing - Kansas City	3508
Viola	3908
Arbuckle	4055

~~RECORDED~~

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

DEC 30 1949

ST. JOHNS, MISSOURI

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above described.

CROWN OIL COMPANY, INC.

*Henry Searak, Officer*

Subscribed and sworn to before me this 29th day of December, 1949.

Notary Public

My commission expires September 21, 1953.

PLUGGING  
FILE SEC 21 T 23 R 13W  
BOOK PAGE 131 LINE 45