

API NUMBER 15-185-22863-6000

LEASE NAME SCHULZ

WELL NUMBER 1-20

330 Ft. from (S) Section Line

4660 Ft. from (E) Section Line

SEC. 20 TWP. 23 RGE. 13 (XX) or (W)

COUNTY STAFFORD

Date Well Completed 8-26-92

Plugging Commenced 8-26-92

Plugging Completed 8-26-92

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR CHIEF DRILLING, INC.

ADDRESS 120 S. Market, #300 Wichita, Kansas 67202

PHONE#(316) 262-3791 OPERATORS LICENSE NO. 5886

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 25, 1992 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 4005'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		0	255'	8 5/8"	255'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

50 sx. @ 820', 50 sx. @ 280', 10 sx. @ 40', 15 sx. in rathole

Total: 125 sx. 60/40 Pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc.

License No. 6039 9-1-92

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

RECEIVED  
 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chief Drilling, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

SEP 1 1992

L. D. Davis

(Employee of Operator, CONSERVATION DIVISION of Wichita, Kansas)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis

L. D. DAVIS


(Address) R.R. 1 Box 183 B Great Bend, KS.

SUBSCRIBED AND SWORN TO before me this 28th day of August, 1992

Bessie M. DeWerff

Notary Public  
Bessie M. DeWerff

My Commission Expires: 5-20-93



15-185-22863-0000

DRILLER'S WELL LOG

COMMENCED: 8-17-92  
COMPLETED: 8-26-92

CHIEF DRILLING, INC.  
SCHULZ #1-20  
SE SW SW Sec. 20-T23S-R13W  
Stafford County, KS.

Elevation: 1892 GR 1897 KB

0 - 255 Sand & Shale Surface  
255 - 1480 Red bed W/shale  
1480 - 2160 Shale & Lime  
2160 - 4005 Lime & Shale  
4005 RTD

FORMATION DATA:

Anhydrite 781 (+1116)  
Base/Anhy. 805 (+1092)  
Heebner 3344 (-1447)  
Brown Lime 3482 (-1585)  
Lansing 3502 (-1605)  
BKC 3742 (-1845)  
Viola 3868 (-1971)  
Simpson Shale 3906 (-2009)  
Arbuckle 3966 (-2069)  
RTD 4005 (-2108)

SURFACE CASING:

8 5/8" set @ 255' W/160 sx.  
60/40 Poz, 2% Gel, 3% CC


A F F I D A V I T

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

L. D. DAVIS of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

L. D. Davis  
L. D. Davis

Subscribed and sworn to before me this 31st day of August, 1992



My Commission expires: 5-20-93

Bessie M. DeWerff  
Notary Public: Bessie M. DeWerff

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 1 1992  
CONSERVATION DIVISION  
Wichita, Kansas