

15-185-21464-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 20 TWP. 23 RGE. 13 E/W
 Location as in quarters or footage from lines:
C SW NW SW

| | | | |
|--|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Lease Owner Oil and Gas Corporation
 Lease Name Schultz Well No. 1
 Office Address 702 Bitting Building, Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): D&A
 Date Well Completed 11-26-81
 Application for plugging filed 11-26-81
 Plugging commenced 11-26-81
 Plugging completed 11-26-81
 Reason for abandonment of well or producing formation D&A

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. METZ

Producing formation NA Depth to top NA bottom NA T.D. 4000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size | Put in | Pulled Out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 85/8" | 401' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

- Heavy mud to 660' circulated with 60 sacks cement at 660'
- Mud to 300' - 40 sacks cement
- Mud to 40' solid bridge
- 10 sacks cement to surface
- 10 sacks cement in rathole
- 5 sacks cement in mouse hole
- 50/50 poz, 2 % gel, 3% Cal.
- 3 sacks cement in water well

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa Fe Drilling Co.
1346 North Woodlawn, Wichita, Kansas 67208

STATE OF Kansas COUNTY OF Sedgwick, ss.

Philip M. Knighton (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) [Signature]
702 Bitting Bldg., Wichita, Kansas
 (Address) 67202

SUBSCRIBED AND SWORN TO before me this 3rd day of May, 19 82

Kathleen C. Lauer
 Notary Public.

My Commission expires: 11-6-82



MAY 3 1982 5-3-82

CONSERVATION DIVISION
 Wichita, Kansas