

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Stafford County, Sec. 10, Twp. 22, Rge. 13 (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW NW SW
Lease Owner Circle Oil Company, Inc.
Lease Name Boileau Well No. 1
Office Address 500 Bitting Building Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 11-12-66 19
Application for plugging approved 11-13-66 19
Plugging commenced 11-14-66 19
Plugging completed 11-21-66 19
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving
Producing formation Depth to top Bottom Total Depth of Well 3852 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	294	None
				5 1/2	None	2829

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar. Measured T. D.

Sanded to 3500'. Dumped 5 sacks of cement. Working pipe. Shot pipe at 2900' and 2800'.

Circulating. Spudded on mud bridge at 2000'.

Circulating. Spotted 60 bbl of oil.

Working pipe. Pulling pipe.

Squeezed well with 10 sacks of mud and 75 sacks of cement.

11-29-66
RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of November, 19 66

My commission expires May 27, 1969

Notary Public.

DRILLERS LOG
BOILEAU NO. 1

CASING RECORD:	COMPANY: Circle Oil Co., Inc.	DESCRIPTION:
8-5/8" @ 294' w/235 sax cement	CONTRACTOR: Sage Drilling Co.	SW NW SW Sec. 10-22S-13W Stafford Co., Kansas
TOTAL DEPTH: 3850'	COMMENCED: October 4, 1966	Elevation: 1897KB
	COMPLETED: October 12, 1966	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Clay	0	30	
Sand & Clay	30	294	
Red Bed	294	750	
Anhydrite	750	775	
Shale	775	1410	
Lime & Shale	1410	2100	
Shale & Lime	2100	2947	
Lime & Shale	2947	3316	
Shale	3316	3364	
Lime	3364	3382	
Lime & Shale	3382	3606	
Lime & Shale w/Chert	3606	3682	
Chert	3682	3721	
Shale & Lime	3721	3850	

RECEIVED
STATE CONSERVATION COMMISSION

DEC 6 1966

CONSERVATION DIVISION
WICHITA, KANSAS

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING COMPANY, INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 18th day of October, 1966.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.