

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 10 Twp. 22 Rge. (#) 13 (W)

Location as "NE/CNW/SW" or footage from lines SE - NW - SW

Lease Owner Herman George Kaiser, Oil Producer

Lease Name Hahn Well No. 2

Office Address Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19 _____

Application for plugging filed _____ 19 _____

Application for plugging approved _____ 19 _____

Plugging commenced _____ 5 - 10 19 57

Plugging completed _____ 5 - 15 19 57

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundege

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	305	None
				5 1/2	3779	2592.86

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand from 3450 to 3430 - dumped 5 sks cement - pulled casing - mudded hole to 250' - set plug and 10' rock bridge - dumped 5 sks cement with bailer - bailed fluid out of surface pipe - dumped 15 sks cement on plug - mudded to 20' - set rock bridge - dumped 5 sks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company License # 236

Address Box 569 Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
I, W. J. Hall (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. J. Hall

SUBSCRIBED AND SWORN TO before me this 27 day of May, 1957

My commission expires _____

(Address) _____
W. J. Hall
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FIL SEC 10 T. 22 R. 13W
BOOK PAGE 10 LINE 5

JUN 3 1957 6-3-57

CONSERVATION DIVISION
Wichita, Kansas